


CITY OF LAKEWOOD
 COMMUNITY DEVELOPMENT DEPARTMENT
 BUILDING & SAFETY
 (562) 866-9771 Ext. 2350

TYPICAL WATER HEATER IN SHED

Minimum Requirements
 Contact Building & Safety Section For Additional Information



An air pressure test is required on the new gas line, if new gas line exceeds a total of six feet. The test consists of pumping air into the new gas line to a pressure of 10 psi for a period of 15 minutes without loss in pressure. Test is to be witnessed by inspector.

Shed clearance required to side property line is 30 inches.

- Approved Gas shut off valve required ahead of gas flex connector.
- Gas flex connector limited to 3 feet in length.
- 6" clearance required in front of water heater.